



**CITY OF ROCKY FORD**  
**PROJECT NO. 202310-223**  
**WALNUT AVENUE PHASE 2**  
**ASPHALT PAVING PROJECT**

**NOTICE TO BIDDERS**

Separate Bids for the construction of PROJECT NO. 202310-223 ASPHALT PAVING PROJECT will be received by the City of Rocky Ford, 203 S Main St., Rocky Ford, CO. 81067, **until 5:00 pm local time on the 6<sup>th</sup> day of June 2023**. Please address the bids to City Manager, Shannon Wallace.

The winning bidder will be required to do the following:

1. Provide the City with a copy of the certificate of insurance with the City named as additional insured.
2. After the award of the contract and before the start of work, you will be required to attend a preconstruction meeting with representatives of the City. We will discuss special conditions regarding this project.

No bids will be received or accepted after the above specified time for the opening of Bids. Bids submitted after the designated hour will be deemed invalid and returned to the Bidder. The City of Rocky Ford has the right to refuse any and all bids presented by all contractors.

# **INSTRUCTIONS TO BIDDERS**

## **PROJECT DESCRIPTION**

The work to be performed under this contract consist of the rehabilitation and reconstruction of 49,984 square feet of roadway on Walnut Avenue. **All materials, construction, and workmanship shall conform to the Colorado Department of Transportation Standard Specifications for Road and Bridge Construction.**

## **SCOPE OF WORK**

The contractor shall furnish all labor, equipment, materials, and services necessary to reconstruct the roadbed and install a 3" lift of hot asphalt on the entirety of 49,984 square feet of the roadbed.

- Work hours will be restricted to daylight hours only.
- The contractor will be responsible for all overruns on this project.
- Roadbed to be scarified and all spoils removed and replaced.
- Contractor to include all prep work in the square foot bid.
- Surface shall be graded and compacted by rolling to a uniform surface.
- Contractor shall ensure proper drainage on all segments is achieved.
- Surface preparation shall include installing to grade any manhole and valve risers. The city shall provide all risers at their cost and supply them to the contractor.
- On areas where there is no curb and gutter, the contractor shall cut back and ensure a uniform width and transition into alleys.
- Approaches shall be paved in a manner as to provide a smooth transition to the new pavement surface.
- Compaction shall be proofed by the city prior to applying the HMA (hot mix asphalt).
- Contractor shall clean up and properly dispose of any excess materials and debris resulting from said work being done. The cost of cleanup shall be included in the square foot bid.
- Traffic control shall conform to the 2000 MUTCD (Manual on uniform Traffic Control)
- Project shall be completed within 60 days of the contract award date.

## **STANDARD OF PERFORMANCE**

The City will not award this contract unless the contractor furnishes satisfactory evidence of his/her ability and experience to perform this work, and that he/she has sufficient capital and equipment to enable him/her to prosecute the work successfully and to complete within the time stated in the contract. The contractor shall not sublet any portion of his/her contract. It will be the responsibility of the contractor to visit the site with the Public Works Director.

Upon the bid award and notification of bid acceptance, the contractor has 7 days to mobilize and start work on the project. Failure to start on the agreed date will result in a termination of the contract.



**CITY OF ROCKY FORD**  
**PROJECT NO. 202310-223**  
**WALNUT AVENUE PHASE 2**  
**ASPHALT PAVING PROJECT**

TOTAL SQUARE FOOT BID INCLUDING MOBILIZATION \$ \_\_\_\_\_

TOTAL PROJECT COST \$ \_\_\_\_\_

COMPANY NAME \_\_\_\_\_

ADDRESS: \_\_\_\_\_

\_\_\_\_\_

PHONE NUMBER: \_\_\_\_\_

PRINTED NAME: \_\_\_\_\_

SIGNATURE: \_\_\_\_\_

TITLE: \_\_\_\_\_